

# UP MEHRAUNI - II URJA PRIVATE LIMITED

5<sup>th</sup> Floor, B-517, Kanakia Zillion, LBS Marg, Kurla (W), Mumbai-400070 MH

## Purchase Order

Ref: UPMEH2/PO/04

Date: May 14<sup>th</sup>, 2024

To ,

M/S Vaishu Construction,  
Manda Khas, Tahsil- Meja  
Dist- Prayagraj, UP- 212104.  
Mob: 9559726213/9125917987  
E-mail: [mconstructionmanda@gmail.com](mailto:mconstructionmanda@gmail.com)

Sub: - Installation of MMS and DC work of 9 MW at UP Mehrauni-II Urja Private Limited.

Dear Mrs. Varsha,

With reference to above, we are happy to place the order for following scope of work to your company: -

Sr No	Particulars	Unit	Qty	Rate/Qty	Amount
1	<b>Piling of 300 mm Dia and 1.20m/1.50m deep in concrete design mix of M25 grade</b> , including pile marking, boring through crawler mounted DTH, alignment, casting and making pile cap of 200 mm height curing, internal transportation of material etc.	Nos	3,800	2,050	77,90,000
2	<b>Installation of Module Mounting Structure (2PX15)</b> including unloading local transporting within site, erection on tables, alignment and level, tightening of fasteners as per detailed drawing and instructions of client.	Table	496	1,475	7,31,600
3	<b>Installation of Module of 605Wp</b> including local transporting within site, erection on tables, alignment and level, tightening of fasteners as per detailed drawing and instructions of client.	Table	496	1,300	6,44,800
4	Installation, testing and commissioning of DC work as per given scope of work.	MW	9	2,60,000	23,40,000
<b>Total</b>					<b>1,15,06,400</b>
GST @18%					20,71,152
<b>Grand Total inclusive of tax</b>					<b>1,35,77,552</b>



CIN: U40300MH2016PTC285333

# UP MEHRAUNI - II URJA PRIVATE LIMITED

5<sup>th</sup> Floor, B-517, Kanakia Zillion, LBS Marg, Kurla (W), Mumbai-400070 MH

Further terms and condition of work shall be as following: -

## Part A: Work of Piling, MMS & Module Installation

- a) Module shall be unloaded and handed carefully to avoid hair cracks, in case of any damage, cost shall be recovered from vender.
- b) Marking of pile coordinate at site and fixing of column post using templates. Level of all the column post should be uniform as per ground profile and same should be checked using Dumpy Level.
- c) Drilling using collar mounted DTH as desired location and concreting M25.
- d) Making pile cap and curing of entire concreting.
- e) Unloading and installation of module mounting structure.
- f) Module and table alignment in all respect and tightening of table as per specified torque.
- g) Following all the quality compliances as per relevant IS codes, drawings, and instructions of Engineer in charge.
- h) All Internal transportation shall be included in the scope.
- i) All debris and empty boxes shall be stored in store area only.

## Part B: DC Work

- a) DC/AC Trench excavation as per the specification in the approved drawing.
- b) Trench dressing and sand filling /brick lining as per the drawing.
- c) Laying of DC cable and Solar string cable as per the cable schedule
- d) Use of Hume pipe in road crossing, Trench crossing and at the required place as per site requirement.
- e) Back filling of Trench properly.
- f) SCB installation.
- g) LA installation.
- h) Earthing with grid connectivity with required earth pits.
- i) Glanding and Termination of DC and Solar String Cable at both SCB and Inverter End as per specification in the drawing.
- j) Earthing of SCB and Inverter DC side.
- k) Solar String cable dressing.
- l) DC cable rout marking as per the Approved drawing
- m) Pre commissioning testing of SCBs.
- n) Housekeeping and final handing over.
- o) Providing inputs for as built drawing.
- p) Deployment of all the machine, manpower consumable etc. Whereas all the cables, earthing material, cable tie shall be provided by the client.
- q) Handing over of entire system after joint verification of OSEL and O&M team after all the completing punch points.

**2. Schedule of Work Completion:** - The above-mentioned scope of work will be completed within 60 days from the date of issue of purchase order with advance payment.



CIN: U40300MH2016PTC285333

# UP MEHRAUNI - II URJA PRIVATE LIMITED

5<sup>th</sup> Floor, B-517, Kanakia Zillion, LBS Marg, Kurla (W), Mumbai-400070 MH

**3. Payment Terms:** - Following payment terms shall be made on item rates basis on certification of actual work done. Further payments break up as following-

- a. Running bill on certified invoices of work done - 90%.
- b. Retention amount shall be released upon successful completion and handing over - 10%.

**4. Taxes and duties:-** Shall be as following :-

- a) GST 18 % Extra from the above-mentioned rates.
- b) TDS shall be deducted as per applicable rates.

**5. Billing & Shipping Address:**

**Shipping Address:-** UP Mehrauni – II Urja Private Limited, Village Mandakhas, Tehsil Meja, District Prayagraj, U.P.- 212303 **Contact Person:** Mr. Akhilesh Kumar Singh Mob: 9793802847

**Billing Address:** - UP Mehrauni – II Urja Private Limited, Khasra No.- 1651,1652, Tehsil Meja Village Mandakhas, Meja Road District: Prayagraj State: Uttar Pradesh Pin Code: 212303, **GSTN: 09AABCU9793Q1Z4**

Thanking you

For UP Mehrauni – II Urja Private Limited



Authorized Signatory

CIN: U40300MH2016PTC285333